

SOP - INSSOP039 - Moving of HV2 Barriers (Forklift)

Rev 1 – Owner: General Manager – Rentals



ROAD SAFETY RENTAL

1. Objective and Scope

To describe the process of safely moving, storing and handling of HV2 Barriers, utilising a forklift.

2. <u>Responsibilities</u>

The site manager and appropriately competent staff has overall responsibility of ensuring that all elements of this procedure are carried out.

3. <u>General Specifications</u>

General barrier specification are as follows:

- Galvanised Steel Construction
- Length 5845.5mm (230in)
- Width 450mm (18in)
- Height 900mm (35in)
- Weight 2150kg (4740lb)

4. <u>Personal Protective Equipment</u>

The following is mandatory PPE.





Boots Eye Protection

Eye Protection

Ear Protection







Hi Viz

Gloves

Protective Clothing

5. <u>General Safety Points</u>

- a) PPE must be worn at all times refer point 4;
- Moving, storing and handling of barriers involve the use of forklifts. This SOP is to be observed in conjunction with SOP EOSOP-006 (Operating Forklifts) and other state-based legislation on safe operating of a forklift;
- c) All operators driving a forklift must hold a current valid licence

d) Lifting Points

The 6-meter HV2 Barrier must only be lifted from the dedicated centre lifting lug on the top of the barrier with a jib / crane operation.

Bottom lift using forklift tynes is not to be used

e) Under no circumstances is any other product to be placed on the HV2 Barrier when the product is being moved.

6. Moving Barriers

- Barriers should not be more than 300mm above the ground whilst being transported on a forklift.;
- b) An operator may walk beside the barrier to steady the orientation of the barrier; however, this operator must only use one hand and be at an arm's length distance. It is the responsibility of the Forklift Driver to enforce this provision; and
- c) When moving HV2 barriers, speed of travel is not to exceed walking pace.

7. Storing of Barriers within the yard.

a) Typically, barriers should only be stacked 2 high, however barriers can be stacked 3 high, if safe to do so and on flat level concrete with excellent visibility, no cross fall, and clear view line of each barrier stack to ensure barriers are adequately interlocked when stacking.



SOP – INSSOP039 - Moving of HV2 Barriers (Forklift)

Rev 1 – Owner: General Manager – Rentals



If ever in doubt, check with your supervisor prior to stacking barriers.

8. <u>Loading HV2 Barriers</u>

a) Barriers never exceed a height of one barrier when loaded onto a vehicle and are loaded 5 across the bed of the truck (typical semi-trailer).



- b) Barriers are always loaded one unit at a time;
- c) Under no circumstances, is any person permitted to place themselves between the barrier and the loaded truck; and
- d) Barriers are tied down in accordance with the weight guidelines for load restraint applicable to that state. Three (3) chains or more per stack of five (5) barriers.



SOP REVISION UPDATES

Rev 1 dated 16/03/2021

a) New SOP